Dated 16th January 1916.

Notice is hereby given that sealed tenders will be received at the office of the Deputy Commissioner, Kadur District, up to 10th February 1916, for restoring Byaladal minor tank, in the Kadur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1916.

2. The plans, detailed estimate and conditions may be seen at the Deputy Commissioner's Office at Chikmagalur, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Deputy Commissioner. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for restoring Byaladal minor tank, in the Kadur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Deputy Commissioner, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Deputy Commissioner's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

ABSTRACT ESTIMATE OF QUANTITIES.

Items	Per	Quantity
Bund.—Earthwork watering tamping	C. yds.	2,420
Turfing both sides, etc.	S. ft.	2,160
Rough stone work, new	C. yd.	440
Grade stones	Each.	22
Top width stones	,,	22
B. M. Stones	,,	2
Registered No. stones	,,	1
Weir No. I Earthwork excavations	C. yd.	84
Rough stone in mortar	C. ft.	864
Coping burnt stone slabs	S. ft.	238
Rough stone work new	C. yd.	50
Weir No. II—Earthwork excavations	,,	195
Rough stone in mortar	C. ft.	2,609
Coping burnt stone slabs	S. ft.	338
Rough stone, new	C. yd.	72
Sluice work as per design given	R. ft.	30

N. SUBBA RAO,
Offg. Deputy Commissioner.

Notice.

The sale of the second hand Oliver Typewriter No. 5, foolscap size, belonging to the office of the Excise Commissioner, which had been notified in the issue of the *Mysore Gazette* for 6th January 1916, has been adjourned to Thursday, 27th January 1916 at 3 P.M., at the office of the Excise Commissioner, in Mysore, No. 1, Cunningham road, Bangalore. The highest bidder shall pay up the amount of his bid immediately after acceptance and before removal of the machine.

P. RAGHAVENDRA RAO,
Excise Commissioner.

MYSORE PUBLIC WORKS DEPARTMENT.

FORM OF ADVERTISEMENT.

Notice is hereby given that sealed tenders will be received in the office of the Superintending Engineer, Cauvery Reservoir Works Division, up to 15th February 1916, for carting materials from Paschimavahini to Cauvery Reservoir Works (South Bank) and from French Rocks to dam site (North Bank).